

1080279

15-185-21491-0000

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION SW NW NE
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 185-21,966

4290 feet from (S) section line
2310 feet from (E) section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 8625

Lease Name Scheib Well # 2

Operator: VAC Petroleum Co.
Name & Address: 6225 East Kellogg, Suite C
Wichita, KS 67218

County Stafford

Well Total Depth 3690 119.93 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 293

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Box 347, Chase, KS 67524

Company to plug at: Hour: noon Day: 11 Month: December Year: 19 84

Plugging proposal received from Irene Hoover

(company name) Kelso (phone) 316-938-2457

were: 5 1/2" set at 3689' PBD 3490' Perfs at 3499-3333'

1st plug pump 30 sx cement to bottom and stop plug at 3250'

2nd plug squeeze well with 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls, release 8 5/8" rubber plug and pump 100 sx cement.

Plug water well with 5 sx cement

Plugging Proposal Received by J. H. Metz (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 1:15 pm Day: 11 Month: December Year: 19 84

ACTUAL PLUGGING REPORT 5 1/2" set at 3689' PBD 3490' Perfs at 3499-3333'

1st plug pumped 30 sx cement to bottom and stopped plug at 3250', 2nd plug squeezed well with 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls, released 8 5/8" rubber plug and pumped an additional 100 sx cement. Plugged water well with 5 sx cement.

Maximum pressure 750 psi and shut in 100 psi 12-18-84

Remarks: Used 60/40 Pozmix 2% gel 3% cc by Sun Rec 2031' of 5 1/2" (If additional description necessary, use BACK of this form.)

STATE CORPORATION COMMISSION

(did / observe this plugging.

DATE 12-27-84

DEC 18 1984

Signed J. A. Metz (TECHNICIAN)

INV. NO. 6128

CONSERVATION DIVISION
Wichita, Kansas