

1 120428

6-7

API NUMBER 15- 185-21,492-0000

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

SW NE SE, SEC. 27, T. 22 S, R. 12 W/E

1650 feet from S section line

990 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4933

Lease Name Krey Well # 2

Operator: VAC Petroleum Co., Inc.

County Stafford 124.96

Name & Address P.O. Box 780106

Well Total Depth 3845 feet

Wichita, KS 67278-0106

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 274

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Great Bend Casing Pulling, Inc. License Number 4635

Address Great Bend, KS 67530

Company to plug at: Hour: 9 a.m. Day: 7 Month: 6 Year: 19 90

Plugging proposal received from Gary Burke

(company name) Great Bend Casing Pulling, Inc. (phone) 316-793-9711

were: 5 1/2" at 3845' PBDT 3530' Perfs at 3417-84' (3 sets)

1st plug sand back to 3370' and dump 5 sx cement on top of sand through bailer,

2nd plug pump 400 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, release

8 5/8" wiper plug and pump 100 sx cement.

Plugging Proposal Received by Duane Rankin
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 10 a.m. Day: 7 Month: 6 Year: 19 90

ACTUAL PLUGGING REPORT 1st plug sanded 5 1/2" casing back to 3370' and dumped 5 sx cement
on top of sand through bailer,

2nd plug pumped into 8 5/8" surface casing with 400 lbs. hulls, 10 sx gel, 50 sx cement,
10 sx gel, 100 lbs. hulls and 100 sx cement.

Pumping pressure 0-450 psi and shut in 200 psi.

Plate welded on 8 5/8" with 2" collar.

Remarks: Used 60/40 Pozmix 6% gel by HOWCO. Recovered 2602' of 5 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED (with check) observe this plugging.

DATE 6-25-90

JUN 13 1990

Signed Duane Rankin
(TECHNICIAN)

INV. NO. 28470

6-13-90