

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-185-20709-00-00
Spot: CNWNESW Sec/Twnshp/Rge: 27-22S-12W
2310 feet from S Section Line, 1650 feet from W Section Line
Lease/Unit Name: KRANKENBERG Well Number: 1
County: STAFFORD Total Vertical Depth: 3667 feet

Operator License No.: 5614 Conductor Pipe: Size feet: \$119.18
Op Name: HUTCHINSON, WILLIAM S. DBA HUTCH Surface Casing: Size 8.625 feet: 298 WITH 300 SX CMT
Address: PO BOX 521 Production: Size 4.5 feet: 3665 WITH 150 SX CMT
DERBY, KS 67037 Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 12/17/2002 3:00 PM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2537

Proposed Plugging Method: SAND TO 2841' & 4 SX CMT. PUMP 300# HULLS - 10 SX GEL - 50 SX CMT - 10 SX GEL - 100# HULLS - 100 SX CMT. PRESSURE TEST.

Plugging Proposal Received By: RICHARD LACEY WitnessType: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 12/17/2002 6:10 PM KCC Agent: RICHARD LACEY

Actual Plugging Report:
PERFS AT 3036-3488'. OPEN HOLE 3665-67'. SANDED TO 2841' & 4 SX CMT WITH DUMP BAILER. PUMP DOWN 8 5/8" WITH 300# HULLS - 10 SX GEL - 50 SX CMT - 10 SX GEL - 100# HULLS - 100 SX CMT. MAXIMUM PRESSURE 500#. SHUT IN PRESSURE 300#.

RECEIVED
DEC 30 2002
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY COPELAND. RECOVERED 1408' OF 4 1/2" CASING.
Plugged through: CSG

District: 01 Signed Richard M. Lacey (TECHNICIAN)
RECEIVED
DEC 23 2002
KCC Dodge City
INVOICED
DATE 12-31-02
INV. NO. 20030610-01
Form CR-23