

1 080449

R

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-185-21,115-0000
80' S C
N/2 NW NE, SEC. 27, T 22 S, R 12 (W)

4870 feet from S section line
1980 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 8625

Lease Name Scheib Well # 1

Operator: Vac Petroleum Co.

County Stafford 120.12

Name & Address 333 N. Rock Road, Suite 105

Well Total Depth 3696 feet

Wichita, KS 67206

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 298

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050

Address P. O. Box 347, Chase, KS 67524

Company to plug at: Hour: 10:50 am Day: 26 Month: November Year: 1985

Plugging proposal received from Norman Kelso

(company name) Kelso (phone) 316-938-2457

were: 5 1/2" at 3692' PBTD 3679' Perfs at 3339-45'; 3432-36'; 3442-46'; 3462-68';
3504-08'; 3666-70'

1st plug retrievable plug at 3415' and pump 30 sx cement to 3200' - shut in.

2nd plug squeeze well with 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls,
release 8 5/8" rubber plug and pump 125 sx cement.

Plugging Proposal Received by J. H. Metz
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 11:30 am Day: 26 Month: November Year: 1985

ACTUAL PLUGGING REPORT 1st plug set retrievable plug at 3415' and pumped 30 sx cement to
3200' Maximum pressure 1000 psi and shut in 200 psi

2nd plug squeezed well with 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls,
released 8 5/8" rubber plug and pumped 125 sx cement.

Maximum pressure 600 psi and shut in 205 psi

Remarks: Recovered 2824' 5 1/2" casing. Used 60/40 Pozmix 6% gel by Allied.
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE DEC 10 1985

INV. NO. 11388

12-5-85

DEC 5 1985

Signed J. H. Metz
(TECHNICIAN)