

1 060210

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 185-21,966-0000

SE NW NE, SEC. 27, T 22 S, R 12 W/EX

990 feet from N/EX section line

1650 feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 8625

Lease Name Scheib Well # 3

Operator: VAC Petroleum Co.

County Stafford

Name & Address 6225 East Kellogg, Suite C

Well Total Depth 3735 121.39 feet

Wichita, KS 67218

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 297

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A X

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Wheatstate Drilling Company License Number 5149

Address P. O. Box 329, Pratt, KS 67124

Company to plug at: Hour: 4:00 am Day: 4 Month: April Year: 19 84

Plugging proposal received from Steve Fellers

(company name) Wheatstates (phone) 316-793-5513

were: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 3700' with 50 sx cement

2nd plug at 700' with 50 sx cement

3rd plug at 320' with 50 sx cement

solid bridge

4th plug hulls - plug at 40' -- cement to surface with 10 sx cement

6th plug to circulate rathole with 15 sx cement. Plug water well with 5 sx cement

Plugging Proposal Received by Paul A. Luthie  
(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None X

Operations Completed: Hour: 6:00 am Day: 4 Month: April Year: 19 84

ACTUAL PLUGGING REPORT 1st plug at 3700' with 50 sx cement, 2nd plug at 700' with

50 sx cement, 3rd plug at 320' with 50 sx cement, 4th & 5th plugs - solid bridge - hulls -

plug at 40' -- cement to surface with 10 sx cement, 6th plug to circulate rathole with

15 sx cement. Plug water well with 5 sx cement

Remarks: Use 60/40 Pozmix 2% gel by Halliburton  
(If additional description is necessary, use BACK of this form.)

4-12-84  
RECEIVED  
STATE CORPORATION COMMISSION  
APR 12 1984  
CONSERVATION DIVISION  
Wichita, Kansas

INVOICED

DATE 4-12-84

Signed Paul A. Luthie  
(TECHNICIAN)

X INV. NO. 1144  
4-4 APR 25 1984