



# State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

### VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
JAN 16 1970  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Voth of Davidor & Davidor has this

date requested permission to plug the following described well:

Mr. Voth guarantees payment of the plugging fee.

Operator's full Name: Davidor & Davidor, Inc.

Complete Address: 4545 Lincoln Boulevard, Oklahoma City, Oklahoma

Lease Name: Sherman Well No. 1

Location: NE SE Sec. 11 Twp. 23 Rge. 31 (E) (W)

County: Finney Total Depth 4820' Oil Well X

Gas Well      Input Well      SWD Well      D & A X Lost Hole     

Mr. Voth was instructed to plug the well as follows:

8 5/8" to 348' circulated w/ cement. 4 1/2" to 4815' cement.

Top perforations 4770' Plug bottom w/ sand & 5 sacks cement.

Top of cement 4720' Mud 4720' to 340'.

Spot 35 sacks cement 340' to 240'. Mud 240' to 40'.

Plug, Halls & 10 sacks cement 40' to 0'.

Very truly yours,

Conservation Division Agent