

State of Kansas



15-185-20080-0000

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market

WICHITA, KANSAS 67202

WM. H. AVERY	Governor
WILLIAM L. MITCHELL	Chairman
JAMES O. GREENLEAF	Commissioner
HARRY G. WILES	Commissioner
RAYMOND B. HARVEY	Secretary
E. EDWARD JOHNSON	Gen. Counsel

VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
DEC 20 1967
12-20-67
CONSERVATION DIVISION
WICHITA, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Intent to Drill,
filed December 5, 1967

Dear Sir:

Mr. Norman Thompson of Garvey Drilling Company has this date requested permission to plug the following described well:

Mr. Thompson guarantees payment of the plugging fee.

Operator's full Name: Petroleum, Inc.

Complete Address: 300 West Douglas, Wichita, Kansas 67202

Lease Name: Simpson "E" Well No. # 2

Location: SW SW NW Sec. 10 Twp. 21 Rge. 13 (E)(W) W

County Stafford Total Depth 3610' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Thompson was instructed to plug the well as follows:

290' of 8 5/8" surface pipe, cement circulated with 350 sacks. Fill hole with drilling mud to 275', 1st cementing plug, bridge with 1/2 sack of hulls, and cement with 25 sacks. Fill hole with drilling mud to 40', 2nd cementing plug, bridge with 1/2 sack of hulls, and cement with 10 sacks to base of cellar. Bridge and cement rat & mouse holes with 4 sack

Very truly yours,

Arlie Elving
Conservation Division Agent