



15.185.30020.0000

JOHN ANDERSON, Jr. Governor
WILLIAM L. MITCHELL, Chairman
ALVIN F. GRAUERHOLZ Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
ROBT. C. LONDERHOLM Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

FEB 4 1965
2-4-65
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Floyd Butcher of Pan American Petro. Corp has this date requested permission to plug the following described well:

Mr. Butcher guarantees payment of the plugging fee.

Operator's full Name: Pan American Petroleum Corporation

Complete Address: Box 432, Liberal, Kansas

Lease Name: Max Sittner "D" Well No. # 5

Location: NE NE SW Sec. 3 Twp. 22 Rge. 12 (E) (W) W

County Stafford Total Depth 3747 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Butcher was instructed to plug the well as follows:

728' of 8 5/8" surface pipe, cement circulated with 500 sacks.

Fill hole with drilling mud to 250', 1st cementing plug, bridge

with hulls, and cement with 25 sacks. Fill hole with drilling

mud to 40', 2nd cementing plug, bridge with hulls, and cement

with 10 sacks to base cellar. Bridge and cement rat hole with

2 sacks.

Very truly yours,

Archie Elving
Conservation Division Agent