

1 040481

10-23

API NUMBER 15- 185-21,710-0000

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

SE SW NE, SEC. 4, T 22 S, R 12 W/E
2970 feet from S section line
1650 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5086

Lease Name Stargel Well # 1

Operator: Pintail Petroleum Ltd.

County Stafford 121.87

Name & Address
412 E. Douglas, Suite One
Wichita, KS 67202

Well Total Depth 3750 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 314

Abandoned Oil Well Gas Well Input Well SWD Well O&A

Other well as hereinafter indicated

Plugging Contractor Rockhold Engineering, Inc. License Number 5111

Address Box 698, Great Bend, KS 67530

Company to plug at: Hour: 6:30 p.m. Day: 23 Month: 10 Year: 19 90

Plugging proposal received from Deacon Pulley

(company name) Rockhold Engineering, Inc. (phone) 316-792-2506

were: 5 1/2" at 3745' w/150 sx cement, Perfs at 3362-64'

1st plug sand back to 3310' and dump 5 sx cement on top of sand through bailer,

2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, and 125 sx cement.

Plugging Proposal Received by Dan Goodrow (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 7:15 p.m. Day: 23 Month: 10 Year: 19 90

ACTUAL PLUGGING REPORT 1st plug sanded back to 3310' and dumped 5 sx cement on top of sand bridge through bailer,

2nd plug pumped down 8 5/8" surface pipe with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls and 125 sx cement.

Maximum pressure 550 psi and shut in 400 psi.

Remarks: Used 60/40 Pozmix 6% gel by Halliburton. Recovered 2506' of 5 1/2" casing.
(If additional description is necessary, use BACK of this form.)

STATE CORPORATION COMMISSION

INVOICED

DATE 11-6-90

10-30-90

001 30 1990

Signed Stephen J. Puffer (TECHNICIAN)

INV. NO. 29842

CONSERVATION DIVISION
Wichita, Kansas