

1 120447

7-3

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-185-21,384-0000  
SW NE SW, SEC. 4, T 22 S, R 12 W/E  
1650 feet from S section line  
3630 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5228  
Operator: Parrish Corporation  
Name & Address 100 S. Market, Suite 200  
Wichita, KS 67202

Lease Name Sittner Well # 1  
County Stafford 118.46  
Well Total Depth 3645 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 296

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050  
Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 10 a.m. Day: 3 Month: 7 Year: 19 90

Plugging proposal received from Darrell Kelso

(company name) Kelso Casing Pulling, Inc. (phone) 316-938-2457

were: 4 1/2" at 3636' w/125 sx cement, PBDT 3620' Perfs at 3298-3482' (6 sets)

1st plug sand back to 3250' and dump 4 sx cement on top of sand through bailer,

2nd plug pump 4 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"

wiper plug and pump 125 sx cement.

Plugging Proposal Received by Duane Rankin  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 11:30 a.m. Day: 3 Month: 7 Year: 19 90

ACTUAL PLUGGING REPORT 1st plug sanded 4 1/2" casing back to 3240' and dumped 4 sx cement  
on top of sand through bailer,

2nd plug pumped into 8 5/8" surface casing with 400 lbs. hulls, 10 sx gel, 50 sx cement,  
10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 125 sx cement.

Pumping pressure 0-600 psi and shut in 200 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2000' of 4 1/2" casing.  
(if additional description is necessary, use BACK of this form.)

*Rec 7-12-90  
2-2-90*

**INVOICED**

DATE 7-17-90

INV. NO. 28609

Signed Duane Rankin  
(TECHNICIAN)