

7-18 15-185-19396-0000

To: 1 120454
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-D-9172
NE SW NW, SEC. 4, T 22 S, R 12 W/E
3630 feet from S section line
4290 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5228
Operator: Parrish Corporation
Name & Address: 100 S. Market, #200
Wichita, KS 67202

Lease Name Sittner Well # A-2
County Stafford 125.52
Well Total Depth 3862 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 265

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050

Address Box 347, Chase, KS 67524

Company to plug at: Hour: _____ Day: 3 Month: 7 Year: 19 90

Plugging proposal received from Darrell Kelso

(company name) Kelso Casing Pulling, Inc. (phone) 316-938-2457

were: 5 1/2" at 3710' cemented w/100 sx cement Open hole 3710-3862' TOC 3230'

1st plug sand back to 3650' and dump 5 sx cement on top of sand through bailer,
2nd plug pump in 8 5/8" surface casing with 400 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx
gel, 100 lbs. hulls, release 8 5/8" wiper plug and pump 125 sx cement.

Plugging Proposal Received by Duane Rankin
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 3 P.M. Day: 18 Month: 7 Year: 19 90

ACTUAL PLUGGING REPORT 1st plug sanded 5 1/2" casing back to 3660' and dumped 5 sx cement
on top of sand through bailer,

2nd plug pumped into 8 5/8" surface casing with 400 lbs. hulls, 2 sx gel, circulate on
backside. 3rd plug on 7/18/90, ran tubing to 960' and pumped 17 barrels of mud and hulls,

laid down 8 joints of tubing and pumped in with 50 sx cement (3% cc) at 720', then let set
2 1/2 hours, tagged plug at 665' (tubing stacked out), 4th plug pulled tubing to 310' and
circulated cement with 100 sx cement, 5th plug pulled all tubing and filled hole with 20 sx.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2800' of 5 1/2" casing. RECEIVED
(If additional description is necessary, use BACK of this form.)

INVOICED observe this plugging.

DATE 7-30-90

Signed Duane Rankin
(TECHNICIAN)

7-25-90
JUL 25 1990

INV. NO. 28820