

1 120919

15.185.02100-0000

4-23

API NUMBER 15-

NA

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

SW NW SE, SEC. 31, T 22 S, R 11 W, X

1650 feet from S section line

2310 feet from E section line

Lease Name Elmer Allen Well # 1

County Stafford

Well Total Depth 3571 11605 feet

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 10 3/4 feet 223

TECHNICIAN'S PLUGGING REPORT

Operator License # 3613

Operator: Hallwood Petroleum, Inc.

Name: \_\_\_\_\_

Address P.O. Box 378111

Denver, CO 80237

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Klima Well Service License Number 7023

Address P.O. Box 386, Claflin, KS 67525-0386

Company to plug at: Hour: 8 a.m. Day: 23 Month: 4 Year: 19 94

Plugging proposal received from George Hutton

(company name) Hallwood Petroleum (phone) 316-792-2756

vers: 7" at 3571' w/100 sx cement, Arbuckle open hole

1st plug run tubing to bottom and spot 30 sx cement mixed with 2 sx hulls,

2nd plug perforate 7" casing at Base Anhydrite and circulate cement in 7" X 10 3/4" annulus and

7".

Plugging Proposal Received by Steve Durrant (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 1:25 p.m. Day: 23 Month: 4 Year: 19 94

ACTUAL PLUGGING REPORT 1st plug ran tubing to 3515' and pumped 30 sx cement with hulls,

2nd plug pulled tubing to 570' or 20' below perforations in the 7" casing and filled the 7" with 80 sx cement. Pulled all tubing.

3rd plug pumped in 7" casing with 120 sx cement, cement circulated in 7" X 10 3/4" annulus.

4th plug squeezed with 20 sx cement. Shut in with 300%.

*Reed*  
4-27-94

Remarks: Used 60/40 Pozmix 8% gel by HOWCO. No casing recovery.  
(If additional description is necessary, use BACK of this form.)

INVOICED

observe this plugging.

DATE 4-29-94

INV. NO. 40367

Signed *Steve Durrant* (TECHNICIAN)

RECEIVED  
STATE CORPORATION COM

APR 27 1994

CONSERVATION DIVIS  
Wichita, Kansas

Rev.