

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-065-00633-00-01
Spot: NWSWSWNW Sec/Twnshp/Rge: 22-10S-25W
2973 feet from S Section Line, 4961 feet from E Section Line
Lease Name: BRUNGARDT A AND B Well #: 2
County: GRAHAM Total Vertical Depth: 2354 feet

Operator License No.:	String	Size	Depth (ft)	Pulled (ft)	Comments
<u>5364</u>	PROD	4.05	2216		500 SX
Op Name: <u>BEREN CORPORATION</u>	SURF	8.625	202		150 SX
Address: <u>2020 N. BRAMBLEWOOD</u> <u>WICHITA, KS 67206</u>					

Well Type: SWD UIC Docket No: D17005.0 Date/Time to Plug: 03/02/2017 10:30 AM
Plug Co. License No.: 34318 Plug Co. Name: BEREXCO LLC
Proposal Rcvd. from: MARK LEIKER Company: BEREXCO LLC Phone: (316) 772-8649

Proposed Plugging Method: Ordered 250 sx 60/40 pozmix 4% gel cement w/300 # hulls.
Circulated 500 sx cement in casing.
Perforations: 1748' - 1934'.
CIBP at 2008

Plugging Proposal Received By: MARVIN MILLS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 03/02/2017 3:45 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Ran tubing to 1702' and pumped 140 sx cement w/300 # hulls. Good circulation of cement.
Pulled tubing out. Topped off casing with 20 sx cement. Tied on to backside and squeezed
with 10 sx cement. Shut in pressure 300 psi.

GPS: 39.16895 -100.10679

Perfs:


Top	Bot	Thru	Comments
1748	1934		

Remarks: GLOBAL CEMENT TICKET # 2845

Plugged through: TBG

District: 04

Signed



(TECHNICIAN)

CM

MAR 07 2017

KCC WICHITA

MAR 27 2017

RECEIVED

INVOICED

APR - 4 2017

Form CP-2/3