

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-185-20906-00-01
Spot: NWNWSW Sec/Township/Rge: 2-21S-14W
2310 feet from S Section Line, 4950 feet from E Section Line
Lease Name: BIRBECK Well #: 8
County: STAFFORD Total Vertical Depth: 3635 feet

Operator License No.: 5088
Op Name: DARRAH, JOHN JAY, JR.
Address: P.O. BOX 2786
WICHITA, KS 67201

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3433		
PROD	5.5	3635	0	WITH 350 SX CMT
SURF	8.625	371		WITH 300 SX CMT

Well Type: EOR UIC Docket No: E27820.1 Date/Time to Plug: 03/23/2017 9:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Revd. from: WILL DARRAH Company: JOHN JAY DARRAH JR Phone: (316) 219-3390

Proposed Plugging Method: SAND TO 3400' WITH 5 SX CMT. PERFORATE AT 850'. SQUEEZE 50 SX CMT WITH HULLS IN LAST 25 SX CMT. PLUG AT 420' WITH 25 SX CMT. PERFORATE AT 300' & CIRCULATE CMT IN & OUT OF 5 1/2" CASING.

Plugging Proposal Received By: ERIC MACLAREN WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 03/23/2017 12:00 PM KCC Agent: KEN SCOFIELD

Actual Plugging Report:

Perfs:

3/22/17: CBL RAN & FOUND CMT AT 1008' TO 950' & FROM 824' TO 330'. PERFORATED AT 300'-301'. WELL WAS SANDED BACK TO 3400' WITH 5 SX CMT PLACED ON TOP. 3/23/17: BOTTOM PLUG TAGGED AT 3370'. 50 SX CMT PLUG PLACED AT 850'. PULL TBG TO 420' & PUMP CMT INSIDE & PUT OF 5 1/2" CASING. 120 SX CMT WAS USED TO FILL 5 1/2" CASING & ANNULUS. CMT CIRCULATED TO SURFACE. TBG WAS POOH & LAID DOWN. HOLE WAS TOPPED OFF INSIDE & OUT WITH 10 SX CMT. CMT AT SURFACE.


Top	Bot	Thru	Comments
3454	3459		

Remarks: USED 60/40 POZMIX 4% GEL BY COPELAND ACID.

Plugged through: TBG

District: 01

Signed


JA

(TECHNICIAN)

RECEIVED
MAR 28 2017
KCC DODGE CITY

Form CP-2/3

INVOICED
APR - 7 2017