

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-035-30190-00-01  
Spot: NWENWSW Sec/Twnshp/Rge: 7-32S-5E  
2432 feet from S Section Line, 4365 feet from E Section Line  
Lease Name: LUMBERT OWWO Well #: 2  
County: COWLEY Total Vertical Depth: 2024 feet

Operator License No.: 5495  
Op Name: MCPHERSON, BILL AND/OR PENNY M.  
Address: 15256 112TH RD  
WINFIELD, KS 67156

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	1922		100 SX
SURF	8	130		10 SX

Well Type: SWD UIC Docket No: D16327.0 Date/Time to Plug: 03/21/2017 8:00 AM  
Plug Co. License No.: 5495 Plug Co. Name: MCPHERSON, BILL AND/OR PENNY M. DBA MCPHERSON DRILLING  
Proposal Revd. from: BILL MCPHERSON Company: Phone: (620) 229-0216

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: B. J. HOPE Witness Type: PARTIAL  
Date/Time Plugging Completed: 03/22/2017 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

RIH W/TUBING @ 1922', MCPHERSON DRILLING MIXED & PUMPED 20 SXS CLASS A COMMON & DISPLACED IN CASING. DID NOT TAG CEMENT. RIH W/TUBING @ 1922', MCPHERSON DRILLING MIXED & PUMPED 15 SXS CLASS A COMMON & DISPLACED IN CASING. TAGGED CEMENT @ 1860'. RIH W/1" TUBING IN BACK SIDE @ 250', MCPHERSON CIRCULATED 34 SXS CLASS A COMMON TO SURFACE. LAYED DOWN 1" TUBING. RIH W/TUBING ON INSIDE @ 250', MCPHERSON DRILLING MIXED & PUMPED 38 SXS CLASS A COMMON TO SURFACE. CEMENT CIRCULATED. TOP PLUG 72 SXS.

Perfs:

Top	Bot	Thru	Comments
1922	2024	OH	

Remarks: DENIED TA

Plugged through: TBG

District: 02

Signed

DUANE KRUEGER  
(TECHNICIAN)

Form CP-2/3

INVOICED  
APR - 7 2017