

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-015-22923-00-00
Spot: NWSW Sec/Twnshp/Rge: 33-26S-6E
1839 feet from S Section Line, 4878 feet from E Section Line
Lease Name: SALTER Well #: 4
County: BUTLER Total Vertical Depth: 2820 feet

Operator License No.: 5120
Op Name: RANGE OIL COMPANY, INC.
Address: 9412 E. CENTRAL PO BOX 781775
WICHITA, KS 67278

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	2820		75 SX
SURF	8.625	220		220 SX

Well Type: EOR UIC Docket No: E24891.1 Date/Time to Plug: 03/06/2017 8:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: ALAN NATION Company: Phone: (620) 222-4304

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: DUANE KRUEGER Witness Type: PARTIAL
Date/Time Plugging Completed: 03/09/2017 9:30 AM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

Perfs:

SET CIBP @ 2730, DUMP BAILED 2 SXS CEMENT ON TOP OF PLUG. PERFORATED SQUEEZE HOLES 270'-271'. RIH W/TUBING @ 330', QUALITY ESTABLISHED CIRCULATION, MIXED & PUMPED 60/40 POZ MIX 4% GEL, 30 SXS TO SURFACE. LAYED DOWN TUBING. SWEDGED INTO CASING & PUMPED 120 SXS 60/40 POZ MIX 4% GEL TO SURFACE. CEMENT CIRCULATED. TOPPED WELL BACK TO SURFACE W/15 SXS.

Top	Bot	Thru	Comments
2770	2788	CSG	

Remarks: FAILED MIT

Plugged through: TBG

District: 02

Signed

Duane Krueger

(TECHNICIAN)

Form CP-2/3

INVOICED
APR - 7 2017