

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-065-21263-00-01  
Spot: SWSNWSE Sec/Twnshp/Rge: 33-9S-23W  
1631 feet from S Section Line, 1766 feet from E Section Line  
Lease Name: RICE ESTATE Well #: 4  
County: GRAHAM Total Vertical Depth: 4010 feet

Operator License No.: 9292  
Op Name: SCHECK, TIMOTHY DBA SCHECK OIL  
Address: 211 S FRONT ST  
RUSSELL, KS 67665

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	4000		125 SX
SURF	8.625	263		175 SX

Well Type: EOR UIC Docket No: E27369.1 Date/Time to Plug: 03/01/2017 1:00 PM  
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC  
Proposal Rcvd. from: JARAMIE Company: SCHECK, TIMOTHY DBA SCHECK Phone: (785) 483-4096

Proposed Plugging Method: Ordered 450 sx 60/40 pozmix 4% gel cement w/600 # hulls.  
Perforations: 3920' - 3923', 3935' - 3938'.  
Circulated 700 sx cement from 1960'.

Plugging Proposal Received By: MARVIN MILLS WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 03/01/2017 3:15 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Ran tubing to 3718' and pumped 75 sx cement w/300 # hulls. Pulled tubing to 2903' and pumped 75 sx cement w/100 # hulls. Pulled tubing to 1825' and pumped 110 sx cement. Good circulation of cement. Pulled tubing out. Topped off casing with 15 sx cement. Tied on to backside and squeezed with 10 sx cement. Shut in pressure 300 psi.

GPS: 39.22359 -099.89069

Perfs:

Top	Bot	Thru	Comments
3935	3938		
3920	3923		

Remarks: QUALITY OILWELL CEMENTING TICKET # 106

Plugged through: TBG

INVOICED  
APR - 7 2017

District: 04

Signed



(TECHNICIAN)

CM

KCC WICHITA

Form CP-2/3

MAR 07 2017

MAR 27 2017

RECEIVED