

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-015-22048-00-00
Spot: NENWSW Sec/Twnshp/Rge: 2-28S-7E
2226 feet from S Section Line, 4289 feet from E Section Line
Lease Name: BOLLINGER Well #: 2-1
County: BUTLER Total Vertical Depth: 2854 feet

Operator License No.:	String	Size	Depth (ft)	Pulled (ft)	Comments
<u>33889</u>	PROD	4.5	2854		95 SX
Op Name: <u>ALLIANCE EXPLORATION CO., LLC</u>	SURF	8.65	202		100 SX
Address: <u>1800 S BALTIMORE AVE STE 810</u> <u>TULSA, OK 74119</u>					

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/23/2017 8:00 AM
Plug Co. License No.: 33345 Plug Co. Name: BOLLINGER, JERALD
Proposal Rcvd. from: JERALD BOLLINGER Company: _____ Phone: (620) 212-8438

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: JEFF KLOCK Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 03/24/2017 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

Perfs:

RIH ON WIRELINE, PERFORATED SQUEEZE HOLES @ 1900'-1901'. RIH W/TUBING @ 1900', CONSOLIDATED OIL WELL SERVICES ESTABLISHED CIRCULATION MIXED & PUMPED 35 SXS CLASS A COMMON & DISPLACED IN CASING. TAGGED CEMENT PLUG @ 1580'. RIH W/TUBING @ 1550', CONSOLIDATED ESTABLISHED CIRCULATION, MIXED & PUMPED 20 SXS CLASS A COMMON & DISPLACED IN CASING. TAGGED CEMENT PLUG @ 1248'. RIH ON WIRELINE, PERFORATED SQUEEZE HOLES @ 300'-301'. SWEDGED INTO 4 1/2" CASING. CONSOLIDATED MIXED & PUMPED 110 SXS, 60/40 POZ MIX 4% GEL TO SURFACE. CEMENT CIRCULATED. TICKET #52097.

Top	Bot	Thru	Comments
2810	2816	CSG	

INVOICED
APR - 4 2017

Remarks: ILLEGAL INJECTION/COMPLIANCE

Plugged through: TBG

District: 02

Signed

DUANE KRUEGER
(TECHNICIAN)

JK