

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-147-19089-00-00
Spot: SWNESESE Sec/Twnshp/Rge: 1-4S-19W
828 feet from S Section Line, 372 feet from E Section Line
Lease Name: MONT SOL WATER FLOOD U Well #: S-1
County: PHILLIPS Total Vertical Depth: 1299 feet

Operator License No.: 31569
Op Name: BACH, JASON DBA BACH OIL PRODUC
Address: PO BOX 723
ALMA, NE 68920

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	1299		

Well Type: WSW UIC Docket No: _____ Date/Time to Plug: 03/17/2017 9:15 AM
Plug Co. License No.: 99974 Plug Co. Name: GLOBAL CEMENTING
Proposal Rcvd. from: DALE FERLAND Company: BACH, JASON DBA BACH OIL PRO Phone: (785) 302-1435

Proposed Plugging Method: Ordered 175 sx 60/40 pozmix 4% gel cement w/800 # hulls.

Plugging Proposal Received By: RICHARD WILLIAMS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 03/17/2017 11:30 AM KCC Agent: PAT BEDORE

Actual Plugging Report:

Perfs:

Ran tubing to 610' and pumped 80 sx cement w/200 # hulls to circulate cement to surface.
Pulled all tubing. Hooked to 5 1/2" casing and pumped 15 sx cement. Shut in pressure 400 psi.
GPS: 39.72905N -099.40441W

Remarks: GLOBAL CEMENTING TICKET # 2848

Plugged through: TBG

District: 04

Signed _____

Pat Bedore

(TECHNICIAN)

CM

KCC WICHITA

MAR 27 2017

RECEIVED

INVOICED

Form CP-2/3

APR - 4 2017

MAR 20 2017