

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-185-23921-00-00
Spot: NESWNWNW Sec/Twnshp/Rge: 27-22S-14W
4429 feet from S Section Line, 4783 feet from E Section Line
Lease Name: GARVIN TRUST Well #: 1
County: STAFFORD Total Vertical Depth: 3975 feet

Operator License No.: 9090
Op Name: CHARTER ENERGY, INC.
Address: PO BOX 252
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3953	1945	WITH 150 SX CMT
SURF	8.625	523		WITH 235 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/02/2017 10:00 AM
Plug Co. License No.: 32810 Plug Co. Name: PROFESSIONAL PULLING SERVICES LLC
Proposal Rcvd. from: CHRIS SCHOENHOFER Company: CHARTER ENERGY Phone: (620) 793-9090

Proposed Plugging Method: SAND PERF TO 3570' WITH 5 SX CMT. PLUG AT 900' WITH 10 SX GEL & 50 SX CMT. PLUG AT 570' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: KENNY SULLIVAN Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 03/08/2017 6:30 PM KCC Agent: KEN SCOFIELD

Actual Plugging Report:

Perfs:

PERFS WERE SANDED ON ABOUT 2/21/17. PLUG WAS TAGGED AT 1400'. TBG WAS BROUGHT OUT TO WASH THROUGH BRIDGE. 3/3/17: BRIDGE WAS WASHED FOR ABOUT 400' BEFORE BREAKING THROUGH. HOLE WAS WASHED TO BOTTOM. 3/6/17: SAND PLUG PLACED THROUGH TBG WITH 5 SX CMT PLACED ON TOP. 3/8/17: BOTTOM PLUG TAGGED AT 3560'. 5 1/2" CASING WAS CUT AT 1945' & PULLED TO 900'. PLUG AT 900' WITH 10 SX GEL & 50 SX CMT. PLUG AT 570' WITH 50 SX CMT. PLUG AT 40' WITH 30 SX CMT. HOLE FULL OF CMT.

Top	Bot	Thru	Comments
3824	3854		
3620	3662		


Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY OIL WELL CEMENTING.

Plugged through: CSG

District: 01

RECEIVED
MAR 17 2017
KCC DODGE CITY

Signed



(TECHNICIAN)

Form CP-2/3

INVOICED

APR - 7 2017

KMS