

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-015-19162-00-00
Spot: NWSESE Sec/Twnshp/Rge: 3-25S-5E
850 feet from S Section Line, 710 feet from E Section Line
Lease Name: FRANK ROBISON Well #: 22
County: BUTLER Total Vertical Depth: 2460 feet

Operator License No.: 33192
Op Name: CROWN ENERGY COMPANY
Address: 1117 N.W. 24TH ST.
OKLAHOMA CITY, OK 73106

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	7	2459		18 SX
SURF	16	129		0 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/20/2017 8:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICH CLARK/JOHN HILL/H Company: _____ Phone: (405) 526-0111

Proposed
Plugging
Method:

AS PER KCC RULES & REGS

Plugging Proposal Received By: JEFF KLOCK Witness Type: PARTIAL
Date/Time Plugging Completed: 03/21/2017 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

Perfs:

RIH W/TUBING @ 2146, QUALITY WELL SERVICE MIXED & PUMPED 35 SXS CLASS A COMMON & DISPLACED IN CASING. 3-21-2017, PERFORATED SQUEEZE HOLES 250'-251'. RIH W/TUBING ON INSIDE @ 250'. QUALITY MIXED & PUMPED 70 SXS 60/40 POZ MIX W/2 BAGS CEDAR FIBER & 100# HULLS TO SURFACE. LAYED DOWN TUBING, TOPPED BACK TO SURFACE W/10 SXS CEMENT. RIH W/1" TUBING ON BACKSIDE @ 236', QUALITY ESTABLISHED CIRCULATION, MIXED & PUMPED 205 SXS 60/40 POZ MIX 4% GEL, 3 SXS CEDAR FIBER & 200# HULLS TO SURFACE. CEMENT CIRCULATED. TOTAL 275 SXS.

Top	Bot	Thru	Comments
2459	2460	OH	

Remarks: DENIED TA/COMPLIANCE

Plugged through: TBG

District: 02

Signed

Duane Krueger

(TECHNICIAN)

Form CP-2/3

INVOICED

APR - 7 2017