

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-079-34780-00-01
Spot: N2N2NE Sec/Twnshp/Rge: 5-22S-3W
300 feet from N Section Line, 1320 feet from E Section Line
Lease Name: L SCHMIDT Well #: 2
County: HARVEY Total Vertical Depth: 3750 feet

Operator License No.: 33737
Op Name: DELL-RAY INVESTMENTS, INC.
Address: 200 N LAKESIDE DR.
MCPHERSON, KS 67460

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	7	3716		130 SX
SURF	10	290		0 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/16/2017 8:00 AM
Plug Co. License No.: 30280 Plug Co. Name: SUNFLOWER WELL SERVICE, INC.
Proposal Rcvd. from: BUD DAVIS Company: _____ Phone: (620) 755-2653

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: VIRGIL CLOTHIER Witness Type: PARTIAL
Date/Time Plugging Completed: 03/16/2017 4:00 PM KCC Agent: B. J. HOPE

Actual Plugging Report:

Perfs:

PBTD 3265'. NO STRETCH ON CASING - UNABLE TO PULL. SANDED BACK TO 3100'- CAPPED WITH 7 SX CEMENT ON TOP. PERFORATED CASING @ 500' TTIT 500' SPOTTED 60 SX CLASS A CEMENT WITH 175 LBS OF HULLS & 3% CC, WAITED 2 HOURS TAGGED @ 425'. PERFORATED CASING @ 350' TTIT 350' CIRCULATED TO SURFACE WITH 255 SX CEMENT & 25 LBS OF HULLS. CUT HEAD OFF CEMENT FELL 20' TOPPED WITH 5 SX CEMENT.

Remarks: COPELAND OUT OF BURRTON WAS CEMENTER - TICKET #44897. PLUGGED DUE TO DENIED TA 10+ YEARS.

Plugged through: TBG

District: 02

Signed

B. J. Hope

(TECHNICIAN)

INVOICED

APR - 7 2017

Form CP-2/3

JK