

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-115-20420-00-00
Spot: NESENWSE **Sec/Twnshp/Rge:** 5-22S-4E
1804 feet from S Section Line, 1366 feet from E Section Line
Lease Name: LATHROP-HAWK C **Well #:** 5
County: MARION **Total Vertical Depth:** 2486 feet

Operator License No.: 6131
Op Name: DRILLERS & PRODUCERS, INC.
Address: PO BOX 385
NEWTON, KS 67114

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	6	2483		50 SX
SURF	8.625	168		135 SX

Well Type: OIL **UIC Docket No:** **Date/Time to Plug:** 03/14/2017 8:00 AM
Plug Co. License No.: 5870 **Plug Co. Name:** PHILLIPS WELL SERVICE, INC.
Proposal Rcvd. from: BILLY ROGERS **Company:** DRILLERS & PRODUCERS, INC. **Phone:** (620) 382-7212

Proposed Plugging Method: per KCC instruction recover casing if possible

Plugging Proposal Received By: VIRGIL CLOTHIER **Witness Type:** NONE
Date/Time Plugging Completed: 03/14/2017 5:00 PM **KCC Agent:** JONATHAN HILL

Actual Plugging Report:

Perfs:

1) Ran tubing to 2470', pumped 30 sks 60/40/4% cement
2) Loaded hole, ran in with wireline and perf'd at 250' with 4 shots
3) Cut window in surface casing, tied into 6" casing and pumped 90 sks 60/40/4% cement w/ 2% CaCl, cemented to surface

Remarks: CEMENTING COMPLETED BY CONSOLIDATED OIL WELL SERVICES, EL DORADO, KS. TICKET #: 50430

Plugged through: TBG

District: 02

Signed Jonathan Hill 4/11
(TECHNICIAN)

INVOICED

APR - 7 2017