

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-015-23562-00-00
Spot: E2NWNESW Sec/Twnshp/Rge: 6-27S-4E
2307 feet from S Section Line, 3451 feet from E Section Line
Lease Name: NATH Well #: 1A
County: BUTLER Total Vertical Depth: 3018 feet

Operator License No.:	String	Size	Depth (ft)	Pulled (ft)	Comments
<u>32657</u>	PROD	5.5	3017		125 SX
Op Name: <u>GATEWAY RESOURCES, LLC</u>	SURF	8.625	213		130 SX
Address: <u>224 S CRESTWAY</u> <u>WICHITA, KS 67218</u>	T1	2.875	3000		

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/01/2017 8:00 AM
Plug Co. License No.: 5870 Plug Co. Name: PHILLIPS WELL SERVICE, INC.
Proposal Rcvd. from: GARY F. GENSCHE Company: _____ Phone: (316) 684-0199

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: DUANE KRUEGER Witness Type: PARTIAL
Date/Time Plugging Completed: 03/07/2017 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

SET CIBP @ 2980', DUMP BAILED 2 SXS CEMENT ON TOP OF PLUG. PRESSURED CASING @ 100#, HELD OK. PERFORATED SQUEEZE HOLES 265'-266', SWEDGED INTO 5 1/2" CASING. CONSOLIDATED OIL WELL SERVICES ESTABLISHED CIRCULATION & MIXED & PUMPED 110 SXS 60/40 POZ MIX 4% GEL 2% CC W/HULLS TO SURFACE. CEMENT CIRCULATED. CEMENT TICKET #52074. 3-7-2017 TAGGED CEMENT @ 28', TOPPED BACK TO SURFACE W/6 SXS CEMENT.

Perfs:

Top	Bot	Thru	Comments
3016	3017	CSG	
3015	3017	CSG	

Remarks: COMPLIANCE/10 YEAR RULE

Plugged through: TBG

District: 02

Signed DUANE KRUEGER
(TECHNICIAN)

Form CP-2/3

INVOICED
APR - 7 2017

1/8