

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-009-22365-00-00
Spot: NWSWSW Sec/Twnshp/Rge: 1-18S-12W
990 feet from S Section Line, 330 feet from W Section Line
Lease Name: WERNER Well #: 1
County: BARTON Total Vertical Depth: 3431 feet

Operator License No.: 6170
Op Name: GLOBE OPERATING, INC.
Address: PO BOX 12
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3430		150 SX
SURF	8.625	298		175 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/02/2017 8:30 AM
Plug Co. License No.: 8253 Plug Co. Name: G & L WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD STALCUP Company: GLOBE OPERATING INC. Phone: (620) 792-7607

Proposed Plugging Method: Ordered 365 sx 60/40 pozmix 4% gel cement w/500 # hulls and 1400# gel.
Bad holes in casing at ANH.
Emergency plug with rig over hole.
CIBP at 3400'.

Plugging Proposal Received By: RICHARD WILLIAMS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 03/02/2017 5:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Perforated at 1400' and 300'. Ran tubing to 3360' and pumped 1400 # gel followed by 50 sx cement w/150 # hulls. Pulled tubing to 1400' and pumped 60 sx cement w/100 # hulls. Pulled tubing to 775' and pumped 50 sx cement. Pulled tubing to 300'. Circulated cement to surface on casing and surface pipe w/125 sx cement pressured to 300 psi. Pulled tubing and topped off with 15 sx cement.

GPS: 38.50994 -098.60761

Perfs:

Top	Bot	Thru	Comments
3146	3386		

Remarks: BASIC CEMENTING

Plugged through: TBG

INVOICED

APR - 7 2017

District: 04

Signed

Bruce Rodie

(TECHNICIAN)

cm

KCC WICHITA

MAR 27 2017

RECEIVED

MAR 13 2017