

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-163-19397-00-00
Spot: SWNWSENW Sec/Twnshp/Rge: 7-10S-17W
3504 feet from S Section Line, 3906 feet from E Section Line
Lease Name: ROSS Well #: #1 WSW
County: ROOKS Total Vertical Depth: 875 feet

Operator License No.: 5552
Op Name: GORE OIL COMPANY
Address: 202 S ST FRANCIS PO BOX 2757
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	7	870		100 SX
SURF	9.865	250		100 SX

Well Type: WSW UIC Docket No: _____ Date/Time to Plug: 03/07/2017 10:00 AM
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.
Proposal Rcvd. from: LENNY DINKEL Company: GORE OIL COMPANY DBA Phone: (785) 259-1928

Proposed Plugging Method: Located old wsw with fiberglass tubing and submersible pump. Dug out 9 5/8" surface pipe and was full of cement. Records show open hole from 870' - 875'. Pulled submersible pump and 796' of fiberglass tubing out of hole.
Ordered 250 sx 60/40 pozmix 4% gel cement w/500 # hulls.

Plugging Proposal Received By: RICHARD WILLIAMS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 03/07/2017 11:30 AM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Perfs:

Pumped 200 sx cement w/500 # hulls. Maximum pressure 150 psi. Shut in 1 hour. Topped off 7" casing with 25 sx cement. Backside had cement to surface.

GPS: 39.20038 -099.26531

Remarks:

Plugged through: CSG

District: 04

Signed Richard Williams
(TECHNICIAN)

CM

KCC WICHITA

MAR 27 2017
RECEIVED

MAR 8 8 2017

INVOICED
APR - 7 2017

Form CP-2/3