

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-047-21041-00-00
Spot: SWSESENW Sec/Twnshp/Rge: 17-24S-16W
2312 feet from N Section Line, 2304 feet from W Section Line
Lease Name: DUTTON Well #: 3-17
County: EDWARDS Total Vertical Depth: 4415 feet

Operator License No.: 5056
Op Name: F. G. HOLL COMPANY L.L.C.
Address: 9431 E CENTRAL STE 100
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4220		WITH 2 SX CMT
PROD	4.5	4410	2220	WITH 225 SX CMT
SURF	8.625	265		WITH 210 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 03/27/2017 4:05 PM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Revd. from: DAVID BRADY Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: SET CIBP @ 4220' WITH 2 SX CMT. PLUG AT 1140' WITH 10 SX GEL & 50 SX CMT. PLUG AT 300' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: KENNY SULLIVAN Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 03/27/2017 5:30 PM KCC Agent: SCOTT ALBERG

Actual Plugging Report:

CIBP @ 4220' WITH 2 SX CMT ON TOP. 1ST PLUG AT 1140' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 300' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 20 SX CMT. CMT TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
4318	4324		
4276	4282		
4269	4273		

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY WELL SERVICE.

Plugged through: CSG

District: 01

Signed _____

[Signature]
57A (TECHNICIAN)

RECEIVED
MAR 28 2017
KCC DODGE CITY

Form CP-2/3

INVOICED
APR - 7 2017