

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-047-21223-00-00
Spot: SESWNE Sec/Twnshp/Rge: 17-24S-16W
2970 feet from S Section Line, 1650 feet from E Section Line
Lense Name: DUTTON Well #: 4-17
County: EDWARDS Total Vertical Depth: 4384 feet

Operator License No.: 5056
Op Name: F. G. HOLL COMPANY L.L.C.
Address: 9431 E CENTRAL STE 100
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4240		WITH 2 SX CMT
PROD	4.5	4382	2200	WITH 225 SX CMT
SURF	8.625	298		WITH 225 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 03/28/2017 1:00 PM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Revd. from: ROB LONG Company: F.G. HOLL Phone: (620) 793-0915

Proposed Plugging Method: SET CIBP @ 4240' WITH 2 SX CMT. PLUG AT 1140' WITH 10 SX GEL & 50 SX CMT. PLUG AT 330' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: KENNY SULLIVAN WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 03/28/2017 4:00 PM KCC Agent: KEN SCOFIELD

Actual Plugging Report:

SET CIBP @ 4240' WITH 2 SX CMT ON TOP. 1ST PLUG AT 1140' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 330' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 30 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4288	4296		

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY.

Plugged through: CSG

District: 01

Signed Ken Scofield

(TECHNICIAN)

RECEIVED
MAR 29 2017
KCC DODGE CITY

5A

Form CP-2/3

INVOICED
APR - 7 2017