

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-127-19031-00-00  
Spot: SWSENE Sec/Twnshp/Rge: 27-15S-9E  
2970 feet from S Section Line, 990 feet from E Section Line  
Lease Name: C H WHITE Well #: 1  
County: MORRIS Total Vertical Depth: 3125 feet

Operator License No.: 5010  
Op Name: KNIGHTON OIL COMPANY, INC.  
Address: 1700 N WATERFRONT PKY BLDG 100 S  
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
<u>PROD</u>	<u>5.5</u>	<u>3117</u>		<u>0 SX</u>
<u>SURF</u>	<u>8.625</u>	<u>140</u>		<u>0 SX</u>

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 11/29/2016 12:00 AM  
Plug Co. License No.: 6819 Plug Co. Name: SCOTT'S WELL SERVICE INC  
Proposal Rcvd. from: KEN WERNER Company: KNIGHTON OIL COMPANY Phone: (785) 623-8516

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: \_\_\_\_\_ Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 11/29/2016 2:30 PM KCC Agent: JEFF KLOCK

Actual Plugging Report:

Perfs:

RAN TUBING TO 3003'. PUMPED 35 SX 60/40 CEMENT 4% GEL 3% CC WITH COTTONSEED HULLS ON BOTTOM. TAGGED @ 2834', PULLED TUBING. PERFORATED @ 250'. RAN 7 JOINTS IN WELL AND CIRCULATED CEMENT TO SURFACE. PUMPED 50 SACKS CEMENT DOWN CASING. 85 SX 60/40 CEMENT 2% CC AND HULLS @ 250'. FELL IN MIXED 50 SX TO FILL 5 1/2" TO SURFACE AND SURFACE CASING.

Remarks: CONSOLIDATED TICKET #51925.

Plugged through: CSG

District: 02

Signed

Jeff Klock

(TECHNICIAN)

INVOICED

Form CP-2/3

APR - 7 2017