

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-127-19026-00-00
Spot: NWSWSW Sec/Twnshp/Rge: 26-15S-9E
990 feet from S Section Line, 330 feet from W Section Line
Lease Name: OLSEN Well #: 2
County: MORRIS Total Vertical Depth: 3097 feet

Operator License No.: 5010
Op Name: KNIGHTON OIL COMPANY, INC.
Address: 1700 N WATERFRONT PKY BLDG 100 S
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3091		100 SX
SURF	8.625	142		160 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/02/1608 8:00 AM
Plug Co. License No.: 6819 Plug Co. Name: SCOTT'S WELL SERVICE INC
Proposal Rcvd. from: KEN WERNER Company: KNIGHTON OIL COMPANY Phone: (785) 623-8516

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: _____ Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 12/02/2016 11:30 AM KCC Agent: JERRY SPARLING

Actual Plugging Report:

Perfs:

RAN 97 JOINTS TUBING IN WELL. CEMENTED BOTTOM WITH 35 SACKS. TAGGED CEMENT AT 2936'. PULLED TUBING BACK OUT. PERFORATED @ 240' AND RAN 8 JOINTS TUBING IN WELL. PUMPED CEMENT DOWN TUBING, CIRCULATED CEMENT TO SURFACE. CEMENT FELL BACK DOWN HOLE. PUSHED WIPER PLUG DOWN TO 300'. DUMPED SAND ON PLUG. CONSOLIDATED WAS OUT OF CEMENT. CONSOLIDATED RETURNED WITH ANOTHER LOAD OF CEMENT. FILL CASING WITH CEMENT. CEMENT SURFACED TO THE TOP DOWN CASING AND SURFACE PIPE. FILL HOLE WITH CEMENT. USED 140 SACKS CEMENT ON TOP. TOTAL 350 SACKS OF CEMENT USED. 35 SX 60/40 CEMENT 4% GEL 3% CC WITH COTTONSEED HULLS ON BOTTOM. WAITED 1.5 HOURS TAGGED @ 2936 FT. RAN TUBING TO 240'. FILLED 5.5" CASING WITH 75 SX. FELL BACK. WAITED 2 HOURS FILLED TO SURFACE (403 FT) AND SURFACE CASING. 350 SX TOTAL.


Top	Bot	Thru	Comments
2936	3097	CSG	
0	300	CSG	

Remarks: CONSOLIDATED TICKET #51930. SENT TA NOV 9-27-16.

Plugged through: CSG

District: 02

Signed



(TECHNICIAN)

Form CP-2/3

INVOICED

APR - 7 2017