

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-063-22215-00-00
Spot: E2SESWNW Sec/Twnshp/Rge: 12-13S-29W
2970 feet from S Section Line, 1060 feet from W Section Line
Lease Name: ANITA Well #: 1-12
County: GOVE Total Vertical Depth: 4530 feet

Operator License No.: 6039
Op Name: L. D. DRILLING, INC.
Address: 7 SW 26TH AVE
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	4523		600 SX
SURF	8.625	369		300 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/09/2017 10:30 AM
Plug Co. License No.: 32810 Plug Co. Name: PROFESSIONAL PULLING SERVICES LLC
Proposal Rcvd. from: MIKE KASSELMAN Company: L. D. DRILLING, INC. Phone: (620) 793-3051

Proposed Plugging Method: Ordered 300 sx 60/40 pozmix 4% gel cement w/250 # hulls and 10 sx gel.
Perforations: 3982' - 3984', 3994' - 3996', 4024' - 4028', 4051' - 4054', 4063' - 4065', 4087' - 4091', 4115' - 4119', 4295' - 4298'.
DV Tool set at 2241' w/400 sx cement.

Plugging Proposal Received By: MARVIN MILLS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 03/09/2017 4:00 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Ran tubing to 4224' and pumped 10 sx gel followed by 65 sx cement w/250 # hulls. Pulled tubing to 2255' and pumped 140 sx cement. Good circulation of cement. Pulled tubing out and topped casing off with 50 sx cement. Backside is full of cement.

GPS: 38.93884 -100.49728

Perfs:


Top	Bot	Thru	Comments
4295	4298		
4087	4091		
4051	4054		
3994	3996		

Remarks: BASIC CEMENT TICKET # 171814312L

Plugged through: TBG

District: 04

Signed _____



(TECHNICIAN)

CM

KCC WICHITA

MAR 13 2017

MAR 27 2017

RECEIVED

INVOICED

APR - 7 2017

Form CP-2/3