

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-185-12652-00-00  
Spot: SESENW Sec/Twnshp/Rge: 14-21S-12W  
2310 feet from N Section Line, 2310 feet from W Section Line  
Lease Name: GROW M Well #: 1  
County: STAFFORD Total Vertical Depth: 3578 feet

Operator License No.: 5259  
Op Name: MAI OIL OPERATIONS, INC.  
Address: 8411 PRESTON RD STE 800  
DALLAS, TX 75225

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3541	0	WITH 100 SX CMT
SURF	8.625	307		WITH 250 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 03/13/2017 12:00 PM  
Plug Co. License No.: 99977 Plug Co. Name: QUALITY OIL WELL CEMENTING  
Proposal Revd. from: BRENT HOMIER Company: MAI OIL OPERATIONS Phone: (785) 445-2353

Proposed Plugging Method: SAND BACK TO 3490' WITH 5 SX CMT. PERFORATE AT 660'. RTIH TO 660 CIRCULATE INSIDE & OUT.

Plugging Proposal Received By: WADE KLAUS Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 03/15/2017 1:00 PM KCC Agent: KEN SCOFIELD

Actual Plugging Report:

Perfs:

\*\*WELL SQUEEZED AT 3110' - 3442' WITH 150 SX CMT\*\* 3/13/17: RIH WITH 2 3/8" TBG TO 3525'. PUMP 100 SX CMT WITH 300# HULLS & 2% CC. WAIT ON CMT THEN TAG PLUG. TAGGED PLUG AT 2527'. PERFORATE AT 660'. RUN TBG TO 660'. BREAK CIRCULATION WITH FRESH WATER THEN PUMP 150 SX CMT. CMT DID NOT CIRCULATE TO SURFACE ON BACK SIDE. 3/14/17: CMT TAGGED AT 140'. 5 1/2" CASING WAS FILLED TO SURFACE WITH 15 SX CMT. TIED ONTO BACKSIDE & PUMPED 15 SX CMT UNTIL IT PRESSURED UP TO 300 PSI. CMT AT SURFACE.


Top	Bot	Thru	Comments
3541	3578	OH	

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY OIL.

Plugged through: TBG

District: 01

Signed



(TECHNICIAN)

RECEIVED  
MAR 17 2017  
KCC DODGE CITY



INVOICED

Form CP-2/3

APR - 7 2017

KMS