

R LP

Form CP-3
Rev. 6-26-62KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORTRECEIVED
STATE CORPORATION COMMISSION

JAN 28 1966

CONSERVATION DIVISION
Wichita, KansasJ. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, KansasOperator's Full Name Western Petroleum Company, Inc.Complete Address: 925 Patton Road, Great Bend, KansasLease Name Sittner Well No. #1Location NW NE SW Sec. 4 Twp. 22 Rge. 12 (E) (W) WCounty Stafford Total Depth 3640'Abandoned Oil Well X Gas Well Input Well SWD Well D & A Other well as hereafter indicated: Plugging Contractor: Forbes Casing Pulling, Inc.Address: Box 221, Great Bend, Kansas License No. 49Operation Completed: Hour 11:45AM Day 26th Month Jan. Year 1966

The Above well was plugged as follows:

280' of 8 5/8" surface pipe, cemented with 250 sacks. 3640' of 5 1/2" long string, cemented with 100 sacks. Plug back to 3510'. Top perferation 3480'. Bottom of the hole was sanded to 3450', and cemented with 5 sacks, through the dump bailer. 2550' of 5 1/2" long string was recovered from the hole. Fluid was up in the hole. Bridge plug was pushed in fluid to 270', rock bridge from 270' to 260'. 12 sacks of cement was mixed in barrel, and put on plug at 260; through the dump bailer, and let set over-night. Next morning hole was bailed dry, and 13 sacks of cement was added to the plug. Hole was filled with mud to 40'. rock bridge from 40' to 30', and cemented with 10 sacks to the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving
Well Plugging SupervisorDATE 1-28-66INV. NO. 2658-W