

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
FEB 20 1973  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

Operator's Full Name Clinton Oil Co

Complete Address 217 N Water Wichita, KS

Lease Name C.J. Heyen B Well No. 2

Location NE/NW/NE Sec. 31 Twp. 22 Rge. 11 (E) (W) W

County Stafford Total Depth 3549

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated \_\_\_\_\_

Plugging Contractor Knight Casing Pulling Co Inc

Address Box 405 Chase, KS License No. 436

Operation Completed: Hour 1:00 PM Day 19 Month 2 Year 1973

The above well was plugged as follows:

193 ft 13" surface cemented with 225 sacks. 3529 ft 7" long string  
cemented with 200 sacks. Top perf. 3386 ft. Sand to 3375 ft, 6  
sacks cement with bailer. Pulled 1700 ft 7". Set 10 ft rock bridge  
at 200 ft. Fill hole with 7 yds redimix to surface.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: [Signature]  
Well Plugging Supervisor

DATE 2/22/73  
INV. NO. 7003-W