

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORTJ. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217RECEIVED
STATE CORPORATION COMMISSION
OCT 15 1973
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Rains & Williamson Oil Co.

Complete Address 435 Page Court, 220 W. Douglas, Wichita, Kansas

Lease Name Yeager Well No. 1

Location NW SE NW Sec. 30 Twp. 22 Rge. (E) (W) 15

County Pawnee Total Depth 4050'

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated

Plugging Contractor Co. Tools

Address License No.

Operation Completed: Hour 5.30 P Day 11 Month 10 Year 1973

The above well was plugged as follows:

RTD 4050' 8 5/8 csg set at 323' cwc 225 sk.

Gunned pits, circulated heavy mud, set cementing plug at 450' and displaced 50 sk
cmt thru drill pipe. Heavy mud to 240' set cementing plug and displaced 25 sk cmt
thru drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to
base of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: Ben F. Messer
Well Plugging Supervisor

INVOICED

DATE 10/15/73INV. NO. 8014-W