

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, KS 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER N/A  
LEASE NAME Elmer Allen  
WELL NUMBER #1

TYPE OR PRINT  
NOTICE: Fill out completely and  
return to Cons. Div. office  
within 30 days.

1650 Ft. from S. Section Line  
4950 Ft. from E. Section Line  
SEC. 31 TWP. 22 RGE. 11 (E) or (W)  
COUNTY Stafford  
Date Well Complete 8-29-35  
Plugging Commenced 4-23-94  
Plugging Completed 4-26-94

LEASE OPERATOR Hallwood Petroleum, Inc.  
ADDRESS 4582 South Ulster Street Parkway, Suite 1700, Denver, CO 80237  
PHONE # (303) 850-6257 OPERATOR LICENSE NO. 3613

Character of Well Oil  
(Oil, Gas, D&A, SWD, Input, Water Supply Well)  
The plugging proposal was approved on \_\_\_\_\_ (date)  
by \_\_\_\_\_ (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, is well log attached? \_\_\_\_\_

Producing Formation Arbuckle Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_ T.D. 3,568'  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
		0	227'	10-3/4"	227'	None
		0	3,544'	7"	3,544'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugging were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ each set.

Please see information on the back of this form.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Halliburton Drilling Company License No. 5929  
Address 1102 E. Eight, P.O. Box 428, Hays, Kansas 67601  
NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: HALLWOOD PETROLEUM, INC.

STATE OF COLORADO, COUNTY OF DENVER, ss.

Bruce Hoffman, (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Bruce Hoffman  
(Address) \_\_\_\_\_

SUBSCRIBED AND SWORN TO before me this 4th day of May, 1997.

Ada M. Christian  
Notary Public

My Commission Expires: 9/1/97

*Reed*  
*4-1-94*

- 04/23/94 TIH w/ tbg to 3,516'. RU Halliburton, pumed 30 bbls water via tbg, then 30 sxs 40/60 POZ 8% gel w/ 100# hulls. FL @ surface, pull tbg up to 570'. Pumped via tbg, 5 sxs gel followed by 80 sxs 40/60 POZ 8% gel w/ cmt to surface & water out 10-3/4". Pulled out tbg, pumped 120 sxs 40/60 POZ 8% gel via 7" csg w/ cmt to surface out 10-3/4". Squeezed 20 sxs 40/60 POZ 8% gel out @ 300 psi. Closed in valves w/ Duan Rankin Stateman on location. Release Rig & trucks. Ready to bury cement.
- 04/25/94 Move out tbg & wellhead connections. Dig out cmt & put in pits. Cmt 25' down to cmt in csg, cut & cap off csg. Unhook & tank down electrical lines. Start to cover up cmt. SDON.
- 04/26/94 Finish covering cmt. Take down power poles & spool up wire. Load-up poles, wire & control box. Release dozer.