

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

HODGEMAN County, Sec. 9 Twp. 22S Rge. 22W (E) (W)

Location as "NE/CNW/SW" or footage from lines G NW SW

Lease Owner SHELL OIL COMPANY

Lease Name UNRUH Well No. 1-19

Office Address 1700 BROADWAY, DENVER, COLORADO

Character of Well (completed as Oil, Gas or Dry Hole) DRY HOLE

Date well completed 4-11 1963

Application for plugging filed 4-12 1963

Application for plugging approved 4-12 1963

Plugging commenced 4-12 1963

Plugging completed 4-13 1963

Reason for abandonment of well or producing formation DRY HOLE

If a producing well is abandoned, date of last production _____ 19____

Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well HUGH E. SCOTT, LIBERAL, KANSAS

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4575 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
CLAY, SAND & SHALE	SURFACE CSG.	-0-	260'	8-5/8"	260'	NONE

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with mud up to 250'. Put in hulls, plug & 35 sx. cement through drill pipe. Filled with mud to 40'. Put in plug, hulls & 15 sx. cement. Job done by Halliburton.

Job completed at 5:30 a.m. 4-13-63.

RECEIVED
STATE CORPORATION COMMISSION

APR 17 1963

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor SIERRA PETROLEUM CO., INC.

Address 208 PETROLEUM BUILDING, WICHITA 2, KANSAS

STATE OF KANSAS COUNTY OF RUSSELL, ss.

T. R. SULLIVAN, TOOLPUSHER (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) T. R. Sullivan T. R. SULLIVAN, TOOLPUSHER

BOX 232, RUSSELL, KANSAS

(Address)

SUBSCRIBED AND SWORN TO before me this 16TH day of APRIL, 1963

My commission expires 10-17-63

Geray Dietz
Notary Public.



SHELL - UNRUH NO. 1-9
 NW SW Section 9-22S-22W
 East Oppy Field
 Hodgeman County, Kansas

0 - 230 unconsolidated surface sediments
 895 red beds & shale
 1065 anhydrite
 1420 shale
 1440 lime
 1665 shale
 1850 siltstones
 2385 limestone w/interbedded shales
 3170 predominantly shale w/some limestone stringers
 3275 shale
 3550 predominantly shale w/some limestone stringers
 3605 shale & siltstone
 3690 lime
 3760 shale
 3814 lime & shale - Top Heebner Shale
 3834 shale - Top Toronto Limestone
 3850 limestone - Top Douglas Shale
 3874 shale - Top Lansing KC Limestone
 4180 predominantly limestone w/some shale - Base Lansing KC
 4250 lime & shale - Top Marmaton Limestone
 4342 lime & shale - Top Fort Scott Shale
 4402 limy shale - Top Cherokee Shale
 4495 interbedded lime & shale - Top Mississippi-Osage
 4505 dolomite
 4520 fractured chert
 4525 shale
 4545 lime
 4575 dolomite
 4575 Total Depth

Casing Record

8 5/8" cem 260 with 225 sax

RECEIVED
 STATE CORPORATION COMMISSIONER

APR 17 1963

CONSERVATION DIVISION
 Wichita, Kansas