

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

Pawnee County. Sec. 18 Twp. 22 Rge. 15 (E) W (W)

Location as "NE/CNW&SW&" or footage from lines NW NW SW

Lease Owner Musgrove Petroleum Corporation

Lease Name Jones "C" Well No. 1

Office Address 518 Petroleum Building, Wichita, Kansas.

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed October 11, 19 53

Application for plugging filed October 11, (verbally) 19 53

Application for plugging approved October 11, " 19 53


Plugging commenced October 11, 19 53

Plugging completed October 11, 19 53

Reason for abandonment of well or producing formation Dry hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well

Producing formation None Depth to top Bottom Total Depth of Well 4015 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	854'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with heavy mud to 300'.
Set bridging plug with 20 sacks cement.
Filled hole to 20'. Set bridging plug with 10 sacks cement.

10-17-53

FILED
STATE COMMISSION
NOV 11 1953
CONSERVATION DIVISION
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Musgrove Petroleum Corporation,
Address 518 Petroleum Building, Wichita, Kansas.

STATE OF Kansas, COUNTY OF Sedgwick, ss.

I, Gordon L. Koelling (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Gordon L. Koelling
518 Petroleum Building, Wichita, Kansas.
(Address)

SUBSCRIBED AND SWORN to before me this 14th day of October 19 53.

Thelma L. Stinson
Notary Public.

My commission expires September 24, 1956.

PLUGGING
FILE SEC 18 T 22 R 15W
BACK PAGE 135 LINE 40

CONTRACTOR'S WELL LOG

COMPANY:	Musgrove Petroleum Corporation
CONTRACTOR:	Musgrove Petroleum Corporation
FARM:	JONES C #1
LOCATION:	NW NW SW, Section 18-22S-15W Pawnee County, Kansas.
COMMENCED:	September 28, 1953
COMPLETED:	October 11, 1953

0	20	Clay
20	250	Sand and shale
250	310	Blue shale
310	430	Shale & Red bed
430	550	Sand and shells
550	705	Shale & shells
705	1065	Red bed, shells & blue shale
1065	1735	Shale & shells
1735	3305	Lime & shale
3305	3463	Lime
3463	3670	Lime & shale
3670	3990	Lime
3990	4015	Arbuckle
	4015	Rotary Total Depth.

Set 8-5/8" surface pipe at 854' with 350 sacks cement.

Dry and Abandoned.

STATE OF KANSAS)
) SS.
 COUNTY OF SEDGWICK)

I, GORDON L. KOELLING, do hereby certify that the above and foregoing is a true and correct copy of the log of the JONES C #1, NW NW SW, Section 18-22S-15W, Pawnee County, Kansas, as reflected by the files of the Musgrove Petroleum Corporation.

MUSGROVE PETROLEUM CORPORATION
 BY Gordon L. Koelling
 Secretary-Treasurer

Subscribed and sworn to before me, a Notary Public, in and for Sedgwick County, Kansas, this 14th day of October, 1953.

William A. Stinson
 Notary Public

My commission expires September 24, 1956.

PLUGGING
 FILE SEC 18 T 22 R 15W
 BOOK PAGE 135 LINE 10

EDMUNSON