


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Pawnee County, Sec. 20 Twp. 22S Rge. 15 (E) 15 (W)
Location as "NE/CNW/SW" or footage from lines C SW/4 SW/4 SE/4
Lease Owner: Stearns Petroleum, Inc.
Lease Name: Stromer Well No. 4
Office Address: Box 313, Russell, Kansas
Character of Well (completed as Oil, Gas or Dry Hole): Dry Hole
Date well completed: April 5, 1956
Application for plugging filed: April 4, 1956
Application for plugging approved: April 4, 1956
Plugging commenced: April 5, 1956
Plugging completed: April 5, 1956
Reason for abandonment of well or producing formation: Dry

If a producing well is abandoned, date of last production: None 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well: Mr. Rives
Producing formation: Depth to top: Bottom: Total Depth of Well: 4100 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

8-5/8" Surface casing at 212 feet with 200 sacks Pozmix.
Cement circulated

Filled hole with mud. Squeezed with Halliburton pump truck through swedge in 8". Pumped HOWCO plug to 195' with 65 sacks cement on plug.

Casing shut in at surface.

Job complete at 1:30 A.M., April 5, 1956

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor: Stearns Petroleum, Inc.
Address: Box 313, Russell, Kansas

STATE OF KANSAS, COUNTY OF RUSSELL, ss.
R. V. Appling (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *R. V. Appling*
Field Superintendent
Box 313, Russell, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 5th day of April, 1956

My commission expires April 5, 1958

Betty Lou Miller
Betty Lou Miller Notary Public.

PLUGGING
FILE SEC 20 T 22 S 15 W
BOX 313 LINE 38

4-11-56

STROMER #1

Operator: Stearns Petroleum, Inc.
 Contractor: Stearns Petroleum, Inc.
 Commencement Date: March 15, 1956
 Completion Date: April 5, 1956
 Elevation: 2007' K. B.
 I. P.: Dry and Abandoned

Location:
 SW SW SE
 Section 20-22S-15W
 Pawnee County, Kansas

Casing Record:

Ran 11 joints 8-5/8 inch casing set at 212 feet. Cemented with 200 sacks of Pozmix and 2 sacks of Calcium Chloride.

WELL LOG

Sand, Clay & Gravel	0	160
Shale & Shells	160	300
Sand & Shale	300	500
Red Bed & Shale	500	965
Anhydrite	965	989
Shale & Shells	989	1985
Shale & Lime	1985	3442
Shale	3442	3447
Shale & Lime	3447	3597
Lime	3597	3860
Shale & Lime	3860	3909
Chert & Lime	3909	3943
Shale & Lime	3943	3979
Shale & Chert	3979	4006
Cherty Lime & Shale	4006	4041
Shale	4041	4058
Dolomite	4058	4100
R. T. D.	4100	

Formation Tops:

Anhydrite	965	(-1042)
Heebner	3442	(-1435)
Douglas	3478	(-1471)
Brown Lime	3556	(-1549)
Lansing-Kansas City	3568	(-1561)
Base Kansas City	3800	(-1793)
Cherty Conglomerate	3877	(-1870)
Viola	3913	(-1906)
Simpson Shale	3953	(-1946)
Simpson Sand	4024-30	(-2017-23)
Arbuckle	4058	(-2051)
R. T. D.	4100	(-2093)

STATE OF KANSAS)
) SS:
 COUNTY OF RUSSELL)

I hereby certify that the above information is true and correct to the best of my knowledge.

O. G. Stearns
 O. G. Stearns, President

SUBSCRIBED AND SWORN TO BEFORE ME, a Notary Public, this 5th day of April, 1956.

Betty Lou Miller
 Betty Lou Miller, Notary Public

My Commission Expires:

April 5, 1958

