


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Stafford County. Sec. 7 Twp. 22S Rge. 12W (E) (W)

Location as "NE/CNW/SW" or footage from lines SE NE NE

Lease Owner Grant Oil Company

Lease Name Crawford Well No. 1

Office Address 518 W-K-H Building, Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Oil

Date well completed April 30 19 51

Application for plugging filed December 26, 19 55

Application for plugging approved December 28, 19 55

Plugging commenced January 6, 19 56

Plugging completed January 7 19 56

Reason for abandonment of well or producing formation Water

If a producing well is abandoned, date of last production November 26, 19 55

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well R. M. Brundege

Producing formation Arbuckle Depth to top 3673 Bottom 3675 Total Depth of Well 3675 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Arbuckle	Oil	3673	3675	10 3/4"	288'	Cemented
				5 1/2"	3673'	2656.86'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with sand to 3665 feet, dumped 5 sacks cement filled to 3625 feet, pulled pipe. Filled hole with mud to 275 feet, put in 10' rock bridge to 265 feet, mixed and run 25 sacks cement to 218 feet, filled hole with mud from 218 to 25', put in 5 feet rock bridge to 20' mixed and run 10 sacks cement from 20' to bottom of cellar.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Arnett Casing Pulling Co.

Address 172 West Third, Hoisington, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.

I, Paul Pfeifer (employee of owner) or (OWNER/OPERATOR) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Paul Pfeifer

1301 McKinley, Great Bend, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 17th day of January, 19 56

My commission expires August 10, 1957

Virginia M. ... Notary Public.

PLUGGING
FILE REC 7 T 22 R 12 W
BOOK PAGE 27 LINE 13

24-2675-S 2-52-20M

1-18-56

CRAWFORD NO. 1

SE/4 NE/4 NE/4 Sec. 7-22-12W Stafford County, Kansas

Rigging up Rotary Tools 4-10-51
 Tearing out Rotary Tools 4-26-51

Ran 15 Jts. of 10 3/4". Set at 288' with 250 sacks of cement.

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>
Shale and sand	0	214
Sand and redbed	214	660
Anhydrite	660	710
Shale, shells and sand	710	1130
Shale, shells and redbed	1130	1480
Lime and shale	1480	3474
Lime	3474	3550
Lime and shale	3550	3605
Chert and shale	3605	3625
Lime and shale	3625	3675 Total Depth

I, Carl D. Dunn, hereby certify that the above log is true and correct, to the best of my knowledge and belief.

Carl D. Dunn

Subscribed and sworn to before me this 21st day of November, 1955.

Doris C. Wright
 Notary Public

My commission expires: March 9, 1959.

PLUGGING
 FILE SEC 7-22-12W 12u
 BOOK PAGE 29 LINE 13

NOV 21 1955
 STAFFORD COUNTY, KANSAS
 NOTARY PUBLIC