

15
KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-185-01397-0000

RECEIVED
STATE CORPORATION COMMISSION

APR 14 1964

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Inger Oil Company

Complete Address: 1020 Central Bldg., Wichita, Kansas

Lease Name Corn Well No. # 1

Location NE SE SE Sec. 6 Twp. 23 Rge. 13 (E) (W)W

County Stafford Total Depth 3912

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Knight Casing Pulling Co.

Address: Box 304, Chase, Kansas License No. 436

Operation Completed: Hour 11:30 PM Day 13th Month April Year 1964

The Above well was plugged as follows:

315' of 8 5/8" surface pipe, cement circulated. 3910' of 5 1/2" long string,
cemented with 100 sacks. Plug back to 3659'. Top perferation 3613'.
Bottom of hole was sanded to 3600', and cemented with 5 sacks. Fluid
was up in the hole. Plug was pushed to 250', with 10' rock bridge, 5
sacks of cement was mixed in barrel, and put on plug through dump bail-
er, and let set over night. Next morning hole bailed down, and 20 sacks
of cement was added to the plug. Hole was filled with mud to 40', with
10' rock bridge, and cemented with 10 sacks to base cellar. 3200' of 5 1/2"
long string was recovered from the hole.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving
Well Plugging Supervisor

DATE 4/15/64

NO. 8957-W