



KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-185-01356-0000

RECEIVED
STATE CORPORATION COMMISSION

SEP 16 1963

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Inger Oil Co.

Complete Address: 1020 Central Bldg., Wichita, Kansas

Lease Name Kelly-Williams Well No. # 1

Location NW NW SE Sec. 7 Twp. 23 Rge. 13 (E) (W) W

County Stafford Total Depth 3942

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated: _____

Plugging Contractor: Knight Casing Pulling Co.

Address: Box 304, Chase, Kansas License No. 436

Operation Completed: Hour 5:30PM Day 12th Month Sept. Year 1963

The Above well was plugged as follows:

202' of 8 5/8" surface pipe, cemented with 200 sacks. 3750' of 5 1/2" long
string, cemented with 150 sacks. Top perferation 3605'. Bottom hole was
sanded to 3590', cemented with 5 sacks. Water was flowing from surface
pipe, a squeeze job was necessary. 15 sacks of Gel mud and 75 sacks of
cement was pumped in the hole, through an 8 5/8" swage in surface pipe,
to a pressure of 250 lbs. This cementing job was done by Globe Cementing
Co.

2800' of 5 1/2" long string was recovered from the hole

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving
Well Plugging Supervisor

DATE 9/16/63
INV. NO. 9940-W