

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT REPORT

FORM CP-3
Rev. 1-8-82

API Number 15-185-21,612-0000

200 Colorado Derby Building
Wichita, KS 67202

Operator's Full Name Green Wolf Oil Company
Complete Address City National Tower, Suite 1850, Oklahoma City, Oklahoma
Lease Name Mc Candless Well No. 1
Location C 5/2 SE NW Sec. 2 Twp. 22 Rge. 12 (East)(West)
County Stafford Total Depth 3588

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated _____

Plugging Contractor Woodman-Iannitti Drilling Co. and Halliburton Co.

Address 1008 Douglas Bldg, Wichita, Kansas License No. _____

Operation Completed: Hour: 6:00 AM Day: 15 Month: May Year: 1982

Plugging Operations attended by Agent?: All Part None

The above well was plugged as follows: Top Anhydrite 610' Elev. 1829 KB

Hole circulated and Filled with mud. 50 sacks cement pumped through
drill pipe at 450'. 30 sacks cement pumped through drill pipe
at 260'. Hole Filled with mud to 40'. Plug and 1/2 sack hulls
pushed to 40' and hole cemented to base of cellar with 10
sacks cement. Rathole cemented with 10 sacks Cement.
Moushok cemented with 10 sacks cement.

Amount of Surface Casing: 8 5/8" - 266 - 225 sacks Common 29 gel 3% cc.

I hereby certify that the above plugging instructions were given as herein stated.

Signed: _____
Conservation Division Agent

I hereby state that I was not present while the above well was being plugged, however, to the best of my knowledge and belief it was plugged as herein stated. A full account for my not being present is as follows:

Sick in bed

Signed: [Signature]
Conservation Division Agent

INVOICED
DATE 6-3-82
INV. NO. 341-W

RECEIVED
STATE CORPORATION COMMISSION

MAY 24 1982

CONSERVATION DIVISION
Wichita, Kansas