

DISTRICT CONSERVATION AGENT'S REPORT

R

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. CW/2 24 SW

LOCATION ~~24 SW 24~~

SEC. 2 TWP. 22 RGE. 12W

Dry Hole _____ Abandoned Oil Well X Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 1 Lease 144ug

Operator Mr. Lloyd Farthing Address Bussell, Kansas

Field _____ County Stafford

Total Depth 3598 Feet.

(Describe briefly the manner in which the well was plugged)

Surface Pipe 8 1/2" - 1745 ft. - Circulated with cement.
3 1/2" casing set at 3590 ft. - Cemented 100 sacks cement.
Filled hole back from bottom to 3585 ft. with shot.
Dumped 3 sacks of cement at 3585 ft. - Shot off
& pulled the 3 1/2" casing - Filled with mud to 1745 ft.
Set Rock Bridge & 15 sacks of cement at 1745 ft.
Mud to 30 ft. - Plug & 10 sacks of cement
at the surface

RECEIVED

2-18-50

PLUGGING
FILE SEC. 2 T. 22 R. 12W
BOOK PAGE 139 LINE 10

Conservation Div. 18 1950
STATE CORPORATION
COMMISSION
KANSAS

C. R. Strong
District Conservation Agent

Date 2-16-50

F