

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission  
Conservation Division  
800 Bitting Building  
Wichita, Kansas

FILE NO. 105-26

LOCATION CSW-22W-S44

SEC. 2 TWP. 22 RGE. 12-W

Dry Hole \_\_\_\_\_ Abandoned Oil Well X Abandoned Gas Well \_\_\_\_\_

I have today completed supervision of plugging of:

Well No. 12 Lease Krupa

Operator Stafford Development Corp. Address Box #294-Tulsa-Okla.

Field \_\_\_\_\_ County Stafford

Total Depth 3614 Feet.

(Describe briefly the manner in which the well was plugged)

Surface Pipe 8 3/4" - 160ft. Circulated with cement.  
6 casing set at 3606 ft. 100 sacks of cement. Plugged  
back to 3600 ft. with chat. Dumped 5 sacks of cement at 3600 ft.  
Shot off & pulled the 6 casing - mud to 160 ft. Set  
Rock Bridge & 15 sacks of cement at 160 ft. mud to 35 ft.  
Plug & 10 sacks of cement at the surface.

Murcan Casing & Pipe Co. Plugging Contractors

STATE CORPORATION COMMISSION

SEP 14 1951

9-14-51

CONSERVATION DIVISION

Wichita, Kansas

District Conservation Agent

**PLUGGING**  
FILE SEC 2 T 22 R 12 W  
BOOK PAGE 105 LINE 26

Date 9-12-51