

KANSAS

FORM CP-3
Rev. 1-8-82

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT REPORT

API Number 15-185-21,612-0000

200 Colorado Derby Building
Wichita, KS 67202

Operator's Full Name Green Wolf Oil Company
 Complete Address City National Tower, Suite 1850, Oklahoma City, Oklahoma
 Lease Name Mc Candless Well No. 1
 Location C 5/2 SE NW Sec. 2 Twp. 22 Rge. 12 (East)(West)
 County Stafford Total Depth 3588
 Abandoned Oil Well Gas Well Input Well SWD Well D&A X
 Other well as hereinafter indicated
 Plugging Contractor Woodman-Lannitti Drilling Co. and Halliburton Co.
 Address 1008 Douglas Bldg, Wichita, Kansas License No.
 Operation Completed: Hour: 6:00 AM Day: 15 Month: May Year: 1982
 Plugging Operations attended by Agent?: All Part None X

The above well was plugged as follows: Top Anhydrite 610' Elev. 1829 KB
Hole circulated and Filled with mud. 50 sacks cement pumped through
drill pipe at 450'. 30 sacks cement pumped through drill pipe
at 260'. Hole Filled with mud to 40'. Plug and 1/2 sack hulls
pushed to 40' and hole cemented to base of cellar with 10
sacks cement. Rathole cemented with 10 sacks Cement.
Mousehole cemented with 10 sacks cement.

Amount of Surface Casing: 8 5/8" - 266-225 sacks Common 2 3/4" 3 3/8 cc.

I hereby certify that the above plugging instructions were given as herein stated.

Signed: _____
Conservation Division Agent

I hereby state that I was not present while the above well was being plugged, however, to the best of my knowledge and belief it was plugged as herein stated. A full account for my not being present is as follows:

Sick in bed

Signed: [Signature]
Conservation Division Agent

INVOICED
DATE 6-3-82
INV. NO. 341-W

RECEIVED
STATE CORPORATION COMMISSION

MAY 24 1982

CONSERVATION DIVISION
Wichita, Kansas