


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

WELL PLUGGING RECORD



Locate well correctly on above Section Plat

Finney County. Sec. 19 Twp. 22 Rge. (E) 31 (W)
Location as "NE/CNW/SW" or footage from lines 100'N and 100'W of Center
Lease Owner N. Appleman Co.
Lease Name Trekell Well No. 1
Office Address 665 Fifth Avenue, New York 22, N. Y.
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed December 13, 1954 19
Application for plugging filed December 16, 1954 19
Application for plugging approved December 16, 1954 19
Plugging commenced January 14, 1955 19
Plugging completed January 15, 1955 19
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production _____ 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well R. J. Phillippe
Producing formation Krider Depth to top 2711 Bottom 2751 Total Depth of Well 2772 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Ogalalla	Water	0	215	8 5/8"	301'	none
Permian	Shale-Lime	215	2772	5 1/2"	2709'	1140'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Mudded up to 371'. Set bridging plug at 371' and ran 30 sacks of cement 371' to 279'. Bridging plug at 279'. Filled with mud to 50'. Ran 20 sacks of cement to 4' under surface. Cut off 8 5/8" 4' below surface and welded plate on top.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Gibson Machine and Tool Co. Halliburton Oil Well Cementing Co.
Address Box 1111, Borger, Texas

STATE OF KANSAS, COUNTY OF FINNEY, ss.
R. W. Lange (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) R. W. Lange
Box 134, Garden City, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 7 day of February, 1955
George C. Skow
Notary Public.

My commission expires January 28, 1958

PLUGGING
FILE SEC 19 T 22 R 31
BOOK 85 LINE 12

CONSERVATION DIVISION
Wichita, Kansas

2-8-55

N. APPLEMAN COMPANY

Trekell #1

Section 19-22-31

Finney County, Kansas

0 - 190'	Sand
190 - 215'	Gravel
215 - 975'	Blue Shale
975 - 1078'	Sand
1078 - 1285'	Blue Shale, Green Shale
1285 - 1565'	Red Bed, Shale
1565 - 1980'	Anhydrite, Shale
1980 - 2128'	Red Bed, Shale
2128 - 2625'	Shale, Anhydrite
2625 - 2710'	Shale, Lime
2710 - 2725'	Sandy Lime
2725 - 2749'	Lime
2749 - 2761'	Shale
2761 - 2772'	Lime

Drillers: M. A. Hill, Bill Mayfield, Dan C. Abrams
Noble Mason and Clarence Phelps

PLUGGING

FILE SEC 19-22-31
BOOK PAGE 85 LINE 12

Done with
1-19-12