

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

Stafford County. Sec. 24 Twp. 22S Rge. 12 (E) W (W)

Location as "NE/CNW%SW%" or footage from lines NW SW NW

Lease Owner B. E. Ash

Lease Name Hayen Well No. 1

Office Address Box 211 Ellinwood, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) dry hole

Date well completed May 14 19 58

Application for plugging filed May 14 19 58

Application for plugging approved May 14 19 58


Plugging commenced May 14 19 58

Plugging completed May 14 19 58

Reason for abandonment of well or producing formation dry hole

If a producing well is abandoned, date of last production _____ 19____

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Frank Broadfoot

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3675 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	COMMENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface pipe		-0-	291.20'	8 5/8"	291.20'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with heavy mud.
Set plug at 240'. Dumped 1/3 sack hulls.
Mixed and dumped 20 sacks cement.
Filled with heavy mud to 40'.
Set top plug at 40'.
Dumped 1/3 sack hulls.
Mixed and dumped 10 sacks cement.
Plugging completed May 14, 1958.

5-26-58

CONS

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Bea Drilling Company

Address Box 211 Ellinwood, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.

B. E. Ash (~~employee of owner~~) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) B E Ash

Box 211, Ellinwood, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 24 day of May, 19 58

My commission expires November 15, 1958
Helsna L. Ash
Notary Public.

PLUGGING.
FILE SEC 24 T. 22 R. 12W
BOOK PAGE 101 LINE 20

B. E. Ash et al

W E L L L O G
 Hayen # 1
 NW SW NW Sec. 24-T22S-R12W
 Stafford County, Kansas

		<u>Elevation</u>	<u>1851 D. F.</u>	<u>1854 K. B.</u>
0 - 120	Sand and clay			
120 - 260	Red bed and shale			
260 - 291	Red bed			
291 - 605	Red bed and shells			
605 - 630	Anhydrite			
630 - 1180	Shale and shells	Heebner	3135-1281	
1180 - 1450	Salt and shale	Toronto	3154-1300	
1450 - 1550	Shale and shells	Douglas	3180-1326	
1550 - 1800	Sandy lime and shale	Brown lime	3267-1413	
1800 - 2210	Lime and shale	Lansing Kansas City	3293-1439	
2210 - 2300	Sandy lime and shale	Viola	3563-1709	
2300 - 2360	Lime and sandy shale	Simpson shale	3600-1746	
2360 - 3045	Shale and lime	Simpson sand	3655-1801	
3045 - 3075	Lime	Arbuckle	3658-1804	
3075 - 3330	Lime and shale	Rotary Total Depth	3675-1821	
3330 - 3495	Lime			
3495 - 3530	Lime and shale			
3530 - 3605	Lime			
3605 - 3659	Shale and lime			
3659 - 3675	Lime			

8 5/8" Surface casing set and cemented at 291.20' with 170 sacks cement.

Drill Stem Test # 1:

3320' to 3345', open 1 hour, recovered 13 feet rotary mud, no show oil, I.B.H.P. 30#, 20 minutes, F.B.H.P. 30#, 20 minutes.

Drill Stem Test # 2:

3655' to 3659', open 1 hour, 30 minutes, recovered 70' of sulphur water. I.F.P. 30#, F.F.P. 45#, I.B.H.P. 1200#, 20 minutes, F.B.H.P. 1080#, 20 minutes.

Drill Stem Test # 3:

3659' to 3663', tool open 1 hour, recovered 15 feet of rotary mud, no show of oil, I.F.P. 30#, F.B.H.P. 220# in 30 minutes.

Dry and Abandoned:

Plugged May 14, 1958.
 Filled hole with heavy mud. Set plug at 240'. Dumped 1/3 sack hulls. Mixed and dumped 20 sacks cement.
 Filled with heavy mud to 40'. Set top plug at 40'.
 Dumped 1/3 sack hulls. Mixed and dumped 10 sacks cement.
 Plugging completed May 14, 1958.

STATE OF KANSAS
 COUNTY OF BARTON ss

B. E. Ash, owner of Bea Drilling Company, being first duly sworn on oath says: That I have knowledge of the facts, statements and matters herein contained and the log of the above described well as filed and that the same are true and correct.

B. E. Ash
 B. E. Ash

Subscribed and sworn before me this 24 day of May, 1958.

Helma L. Ash
 Notary Public

My Commission expires: November 15, 1958

