


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

NORTH



Locate well correctly on above
Section Flat

Stafford County. Sec. 24 Twp. 22S Rge. 12W (E) (W)
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines SE $\frac{1}{4}$ SE $\frac{1}{2}$ SE $\frac{3}{4}$
Lease Owner Anderson-Prichard Oil Corporation
Lease Name Heyen Well No. 1
Office Address Great Bend, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) dry hole
Date well completed 12-7 19 51
Application for plugging filed 12-7 19 51
Application for plugging approved 12-7 19 51
Plugging commenced 12-7 19 51
Plugging completed 12-7 19 51
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well C. D. Stough
Producing formation Depth to top Bottom Total Depth of Well 3800 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out	
			255'	8-5/8"	259'		
			cemented with 200 sacks cement and 2 c.c.				

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Bottom plug set at 240' with 15 sacks cement mixed and poured through drill pipe, top plug 35' below ground level with 10 sacks cement on top.

12-12-51

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Anderson-Prichard Oil Corporation
Address West Tenth Street
Great Bend, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, SS.
Richard Hindery partner of Birmingham-Bartlett Drilling Co. contractor of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Richard Hindery
300 Kaufman Bldg., Wichita 2, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 10th day of December, 19 51.

My commission expires November 29, 1954
Lincoln S. Ginger Notary Public.

23-5091-s 8-50-10M
PLUGGING
FILE SEC. 24 TWP. 22S R. 12W
NOV 20 1951

HEYEN NO. 1

LOCATION: SE $\frac{1}{4}$ SE $\frac{1}{4}$ SE $\frac{1}{4}$ Sec. 24-22-12W
Stafford County, Kansas

OPERATOR: Anderson-Prichard Oil Corp.

CONTRACTOR: Birmingham-Bartlett Drilling Co.

SURFACE CASING: 8-5/8" casing cemented at 255' with
200 sacks cement and 2 c.c.

OIL STRING: None. D & A.

SPUDDED: 11-24-51

COMPLETED: 12-7-51

L O G

(Figures indicate bottom of formation)

0 to 90	Surface sand and clay
230	Shale and shells
565	Red bed
580	Anhydrite
1440	Shale and shells
1570	Shale and lime
1600	Broken lime
1710	Lime
1840	Broken lime
1970	Lime
2635	Shale and shells
2980	Shale and lime
3123	Lime
3290	Shale and lime
3490	Lime
3570	Lime and shale
3590	Viola Chert
3613	Lime
3686	Shale
3690	Arbuckle
3800	Lime
3800	Total Depth

The undersigned Richard Hindery of the Birmingham-Bartlett Drilling Co. hereby certifies that the above is a true and correct log of the formations encountered in drilling the Heyen #1 well as shown on the daily drilling reports.

BIRMINGHAM-BARTLETT DRILLING CO.

BY Richard Hindery 1951

Subscribed and sworn before me
this 10th day of December, 1951.

Walter J. Singer
Notary Public

My commission expires November 29, 1954.

