

WELL PLUGGING RECORD

STATE OF KANSAS
STATE CORPORATION COMMISSION


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

OR

FORMATION PLUGGING RECORD

Strike out upper line
when reporting plug-
ging off formations.

NORTH



Locate well correctly on above
Section Plat

Stafford County, Sec. 10 Twp. 31 Rge. 13 (E) (W)

Location as "NE 1/4 NW 1/4 SW 1/4" or footage from lines. W 1/2 S 8 1/4
Lease Owner: W. B. Campbell
Lease Name: Rathgarn Well No. 1
Office Address: 521 1st Natl. Bank Wichita, Kans.
Character of Well (completed as Oil, Gas or Dry Hole)
Date well completed: May 1943 19
Application for plugging filed: 6-14-47 19
Application for plugging approved: 19
Plugging commenced: 6-16-47 19
Plugging completed: 6-23-47 19
Reason for abandonment of well or producing formation:

If a producing well is abandoned, date of last production: Sept. 1945
Was permission obtained from the Conservation Division or its agents before plugging was commenced?: H. W. Kerr

Name of Conservation Agent who supervised plugging of this well: H. W. Kerr
Producing formation: Aruckle Depth to top: Bottom: 360.6 Total Depth of Well: 360.6 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				10 3/4	188'	None
				5 1/2		2659.90

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Hole was plugged as follows
Ran 10 sacks cement on bottom
mudded hole to 170' ran 15 sacks cement
mudded hole to 25' ran 10 sacks cement

7-29-47

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to: H. P. Faulkner
Address: 521-1st Natl. Bk Bldg
Wichita 2, Kansas

STATE OF Kansas, COUNTY OF Sedgewick, ss.
H. P. Faulkner (employee of owner) or (owner or operator) of the above-described well,
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) H. P. Faulkner

521-1st Natl Bk Bldg (Address)

SUBSCRIBED AND SWORN to before me this 1st day of July, 1947

Elaine Russell
Notary Public.

My commission expires Jan. 14, 1948



PLUGGING
FILE SEC 10 T 31 R 13
BOOK PAGE 48 LINE 8

W. P. FAULKNER
10-21-13
Stafford County, Kansas
ROTHGARN #1

FORMATION	FROM	TO
Surface soil & clay	0	27
Sand	27	65
Hard sand rock	65	85
Hard sand	85	130
Shale	130	188
Sand, shale, shells	188	355
Shale & red rock	355	450
Shale & lime shells	450	685
Shale	685	730
Anhydrite	730	750
Shale & shells	750	945
Sand, shale, shells	945	1285
Shale & lime	1285	1525
Lime	1525	1610
Lime & shale	1610	1715
Lime	1715	2075
Sandy lime & shale	2075	2340
Lime & shale	2340	2440
Shale & lime shells	2440	2500
Lime & shale	2500	2620
Shale	2620	2680
Lime	2680	2715
Lime & shale	2715	2840
Broken Lime and shale	2840	2935
Broken lime	2935	3000
Lime	3000	3200
Shale	3200	3287
Lime	3287	3292
Lime & shale	3292	3296
Lime	3296	3319
Lime - KC	3319	3357
Lime	3357	3452
Lime broken	3452	3497
Shale & lime	3497	3552
Green shale	3552	3572
Shale	3572	3574
Sand	3574	3578

PLUGGING
FILE SEC 10 T 21 R 13 W
BOOK PAGE 118 LINE 8

